

बाबासाहेब भीमराव अम्बेडकर विश्वविद्यालय

विद्या विहार, रायबरेली रोड, लखनऊ -226025

Babasaheb Bhimrao Ambedkar University

(A Central University)

Vidya Vihar, Raebareli Road, Lucknow-226025

Letter No. 3308.....

Date: 07/03/2022

Quotation Notice

Item wise rates of sealed Quotations are invited from approved and eligible contractors of C.P.WD/U.P.P.W.D./M.E.S./Railways/CPSUs/SPSUs for the following work of "Aluminium Partition work under stair at ground floor, construction of Ramp at the entrance of the Building and extension of platform in conference Hall at SAS Building" with an **Estimated cost of Rs. 1,24,258.00**. B.O.Q. of work as per **Annexure-1**. The quotations shall be received by **Spot Quotations** only, addressed to, "**Assistant Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, University, Lucknow-226025**" in the University up to **15/03/2022 4:00 PM**

The quotations are available on the website of the University only and may be download from bbau.ac.in

Conditions:-

1. The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all editions of C.P.W.D. specifications.
3. All material required for completion of work shall conform to latest ISI/CPWD specifications.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be **10 Days**.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/ State Government.
7. Photocopies of registration in Income tax/ Trade tax department should be submitted alongwith the quotation.
8. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
9. University has the right to reject and one or all quotations without assigning any reason.

Encl: As above


* Website In-charge with a request to upload
on University website job.



Registrar

B.O.Q

Name of Work: Aluminum Partition work under stair at ground floor, construction of Ramp at the entrance of the Building and extension of platform in conference Hall at SAS Building.

S. No.	Items	Qty.	Unit	Rate	Amount (Rs.)
1	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16 mm	2.00	each		0.00
2	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	2.00	each		0.00
3	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	4.00	each		0.00
4	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	93.49	kg		0.00
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	21.47	kg		0.00
6	Providing and fixing 12 mm thick prelaminate particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	32.70	sqm		0.00
7	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	9.69	kg		0.00
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	2.50	cum		0.00
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 500x500 mm	5.00	sqm		0.00
10	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	3.00	sqm		0.00
11	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	50.00	kg		0.00
12	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	10.00	sqm		0.00
Total					-


(Dharmesh Kumar)
J.E.


(V.K. Tripathi)
AE / EE